

GOVERNMENT OF PUDUCHERRY
ELECTRICITY DEPARTMENT
KARAIKAL

L.C.E No: 07 /EDK/EEV/AE(T)/2017 - 2018 /1503

DT 10-08-2017

QUOTATION NOTICE

Sub: EDK – Estimate for Bifurcation of load at Seniyarkulam SS-I 315 KVA, Pattammal Nagar in Karaikal – Quotations Called for labour contract – Reg.

Sealed quotations are hereby invited by the Assistant Engineer-Town-I, Electricity Department, Karaikal on behalf of the President of India, from contractors experienced in similar field of work for the works given below. The Quotations should reach this office on or before 5.00 P.M of 23 / 08 /2017 and the same will be opened at 11.00 A.M. on the next day in the chamber of the Assistant Engineer-Town-I. Those tenderers who are willing may be present at that time. If the opening date happens to be a holiday, the next working day will be treated as the opening day:

NAME OF THE WORK: Estimate for Bifurcation of load at Seniyarkulam SS-I 315 KVA, Pattammal Nagar in Karaikal.

Sl. No	Description of work	Approx. quantity	Rate/un it in Rs.	Amount in Rs.
1.	Supply of 30' RCC poles by contractor including transportation.(Specification enclosed).	1 No		
2.	Supply of 24' RCC poles by contractor including transportation.(Specification enclosed).	2 No's		
3.	Erection of 30'RCC pole including excavation of pit and refilling and earthing, concreting.	1 No		
4.	Erection of 24'RCC pole including excavation of pit and refilling and earthing, concreting.	2 No's		
5.	Erection of 24' RCC stud pole.	1 No		
6.	Erection of 30' RCC pole Earthing.	1 No		
7.	Fixing of V cross arm in RCC pole for 11 KV overhead lines.	1 No		
8.	Fixing of 11KV pin insulator with GI pin.	3 No's		
9.	Labour charges for erection of ACSR 7/3.35 conductor including binding etc. Span length of approximately 45 to 50 mts.	495 Mts		
10.	Fixing of three phase cross arm as required	4 No's		

GOVT. OF INDIA
NIC DISTRICT UNIT,
KARAIKAL.
RECEIVED DATE: 17.08.17

Sl. No	Description of work	Approx. quantity	Rate/unit in Rs.	Amount in Rs.
11.	Fixing of LT Pin insulators	6 No's		
12.	Fixing of shackle with metal parts	6 No's		
13.	Fixing of CI Knob and L clamp	4 No's		


 ASSISTANT ENGINEER-TOWN-I
 ELECTRICITY DEPARTMENT,
 KARAIKAL

To

1. Thiru Jeevanandan, 1, Church street, Karaikal
2. Thiru. S.Kathamuthu, Thoodhuponamoolai, 58 Alathur P.O., Neravy
3. Thiru. V. Ranjith, 4, Pillaiyar koil strret, Thoodhuponamoolai, Neravy
4. Thiru. R. Sakthivel, 114 Church Street, Karaikal.
5. Thiru N.Vengadesan, Kathiravan electrical 108, Gnanapragasam street , Karaikal.
6. Notice Board

Copy to:

1. The Junior Engineer/Town- O&M, Electricity Department, Karaikal
2. The National Informatics Officer, National informatics centre, O/O. The Collector, Karaikal.

Copy submitted to:

The Executive Engineer-V
 Electricity Department,
 Karaikal