

**GOVERNMENT OF PUDUCHERRY
ELECTRICITY DEPARTMENT
KARAIKAL**

L.C.E No: 10 /EDK/EEV/AE(T)/2017 - 2018

DT 10-08-2017

QUOTATION NOTICE

Sub: EDK – Estimate for provision of 1 No of 200 KVA Transformer namely Kaziar street SS at Kaziar street in Karaikal – Quotations Called for labour contract – Reg.

Sealed quotations are hereby invited by the Assistant Engineer-Town-I, Electricity Department, Karaikal on behalf of the President of India, from contractors experienced in similar field of work for the works given below. The Quotations should reach this office on or before 5.00 P.M of 23 / 08 /2017 and the same will be opened at 11.00 A.M. on the next day in the chamber of the Assistant Engineer-Town-I, Those tenderers who are willing may be present at that time. If the opening date happens to be a holiday, the next working day will be treated as the opening day:

NAME OF THE WORK: Estimate for provision of 1 No of 200 KVA Transformer namely Kaziar street SS at Kaziar Street in Karaikal.

Sl.No	Description of work	Approx. quantity	Rate/unit in Rs.	Amount in Rs.
1	Erection of D.P structure including erection of 30' RCC poles and concreting 0.6x0.6x1.5 Mts. And coping 0.6x0.6x0.5 in 1:3:6 ratio using 20mm HBG metal, fixing of DP structure materials, stay sets, AB switches, HG fuses, LAS, Pin Insulators, Bed channel, centre support, erection of Transformer, LT feeding arrangement, earth electrode and construction of earth pit, GI wire for Earthing of all metal parts and lightning arrestor. Painting two coats of aluminum paints for all channel, metal parts, etc. and two coats of cement painting, colour painting to RCC poles, etc. including concreting materials such as cement, jelly, sand, etc. excavation and re-filling.	1 No.		
2.	Supplying of 30" RCC Poles by contractor including transportation. (Specification enclosed).	3 Nos		
3.	Earthing of 30" RCC Pole including excavation of pit and refilling and earthing, concreting.	1 No		
4.	Concreting of 30" RCC pole in cement Concrete foundation (.45x0.45x0.45) Mts with ratio 1:3:6 using 20mm HBG metal including cost of concreting materials such as cement, jelly, sand etc. including earthing, excavation and refilling.	1 No		

GOVT. OF INDIA
NIC-DISTRICT UNIT,
KARAIKAL.
RECEIVED DATE: 17-08-17

Sl.No	Description of work	Approx. quantity	Rate/unit in Rs.	Amount in Rs.
5.	Supplying of 24' RCC poles by contractor including transportation. (Specification enclosed).	1 No		
6.	Erection of 24' RCC Pole including excavation of pit and refilling and earthlings, concreting.	1 No		
7.	Fixing of 11 KV pin insulated with GI pin.	6 Nos		
8.	LT feedering Arrangements	2 No's.		
9	Labour charges for erection of ACSR conductor 7/3.35 including binding etc. span length of approximately 45 to 55 Mtrs.	186 Mtrs.		
10	Labour charges for erection of ACSR conductor 7/2059 including binding etc. span length of approximately 45 to 55 Mtrs.	4 No's		
11	Fixing of 3 ϕ cross arm as required	4 No's		
12	Fixing of LT Pin with Insulators	8 No's		
13	Fixing of Metal parts with shackle	8 No's.		
14	Fixing of CI Knob and L clamp	3 Nos		


ASSISTANT ENGINEER-TOWN-I
ELECTRICITY DEPARTMENT,
KARAIKAL

To

1. Thiru Jeevanandan, 1, Church street, Karaikal
2. Thiru. S.Kathamuthu, Thoodhuponamoolai, 58 Alathur P.O., Neravy
3. Thiru. V. Ranjith, 4, Pillaiyar koil strret, Thoodhuponamoolai, Neravy
4. Thiru. R. Sakthivel, 114 Church Street, Karaikal.
5. Thiru N.Vengadesan, Kathiravan electrical 108, Gnanapragasam street , Karaikal.
6. Notice Board

Copy to:

- 1 The Junior Engineer/Town- O&M, Electricity Department, Karaikal
- 2 The National Informatics Officer, National informatics centre, O/O. The Collector, Karaikal.

Copy submitted to:

The Executive Engineer-V
Electricity Department,
Karaikal