

GOVERNMENT OF PUDUCHERRY
ELECTRICITY DEPARTMENT
KARAIKAL

L.C.E No: 11 /EDK/EEV/AE(T)/2017 - 2018

DT 10-08-2017

QUOTATION NOTICE

Sub: EDK – Estimate for provision of 1 No of 200 KVA Transformer namely Chinakannu Chetty street SS at Chinnakannu Chetty street in Karaikal – Quotations Called for labour contract – Reg.

Sealed quotations are hereby invited by the Assistant Engineer-Town-I, Electricity Department, Karaikal on behalf of the President of India, from contractors experienced in similar field of work for the works given below. The Quotations should reach this office on or before 5.00 P.M of 23 / 08 /2017 and the same will be opened at 11.00 A.M. on the next day in the chamber of the Assistant Engineer-Town-I, Those tenderers who are willing may be present at that time. If the opening date happens to be a holiday, the next working day will be treated as the opening day:

NAME OF THE WORK: Estimate for provision of 1 No of 200 KVA Transformer namely Chinakannu chetty street SS at Chinnakannu Chetty Street in Karaikal.

Sl.No	Description of work	Approx. quantity	Rate/unit in Rs.	Amount in Rs.
1	Erection of D.P structure including erection of 30' RCC poles and concreting 0.6x0.6x1.5 Mts. And coping 0.6x0.6x0.5 in 1:3:6 ratio using 20mm HBG metal, fixing of DP structure materials, stay sets, AB switches, HG fuses, LAS, Pin Insulators, centre support, erection of Transformer, LT feeding arrangement, earth electrode and construction of earth pit, GI wire for Earthing of all metal parts and lightning arrestor. Painting two coats of aluminum paints for all channel, metal parts, etc. and two coats of cement painting, colour painting to RCC poles, etc. including concreting materials such as cement, jelly, sand, etc. excavation and re-filling.	1 No.		
2.	Construction of plinth mount for 200 KVA Distribution Transformer (1.5x1.5x2.5)meters including foundation and cement concreting as per department specification	1 No		

GOVT. OF INDIA
NIC DISTRICT UNIT,
KARAIKAL.
RECEIVED DATE: 17-08-17

Sl.No	Description of work	Approx. quantity	Rate/unit in Rs.	Amount in Rs.
3.	Construction of fencing works for 200 KVA Plinth mount Distribution Transformer including provision of gate and passage.	1 No		
4.	Erection charges of 6 way 600 Amps SS Pillar Box	1 No		
5.	Earthing of SS pillar box as per department specification	1 No		
6.	Formation of pillar box	1 No		
7.	Laying charges of 1 no of PVC insulated and PVC sheathed/XLPE power cable of 1.1 KV grade of size 240 Sq mm LT UG cable at direct in ground including excavation and sand cushioning protective covering and refilling the trench etc., as required (0.35x0.75x1m)	75 mts		
8	Supplying of 30' RCC poles by contractor including transportation. (Specification enclosed).	3 No's.		
9	Erection of 30' RCC Pole including excavation of pit and refilling and earthing, concreting.	3 No's.		
10	Supplying of 24' RCC poles by contractor including transportation. (Specification enclosed).	4 No's		
11	Erection of 24' RCC Pole including excavation of pit and refilling and earthing, concreting.	4 No's		
12	Fixing of V Cross arm with clamp (including HT Pin insulators).	2 No's		
13	Fixing of 11KV Disc with metal parts including F clamp.	6 No's.		
14	Supply and transport of HT UG cable 3x50 sq mm as per department specification.	60 mts		
15	Laying of HT UG cable 3x50 sq mm as per department specification(including road crossing pipe line), etc.,	60 mts		
16	Supplying of end termination kit for HT Cable 3x50 sq mm	2 No's.		

Sl.No	Description of work	Approx. quantity	Rate/unit in Rs.	Amount in Rs.
17	END termination charges for HT 3x50 sq mm End termination kit	2 No's.		
18	Fixing of Three phase cross arm with pole clamp	4 No's.		
19	Erection of 7/3.35 ACSR Conductor for a span length of 45 meters to 55 meters	371 mts		
20	Erection 7/2.59 ACSR Conductor for a span length of 45 meters to 55 meters	1278 mts		
21	Erection of LT stay set	1 No		
22	Fixing of SMC Type meter box and automatic street light control box	1 No		


ASSISTANT ENGINEER-TOWN-I
 ELECTRICITY DEPARTMENT,
 KARAIKAL

To

1. Thiru Jeevanandan, 1, Church street, Karaikal
2. Thiru. S.Kathamuthu, Thoodhuponamoolai, 58 Alathur P.O., Neravy
3. Thiru. V. Ranjith, 4, Pillaiyar koil strret, Thoodhuponamoolai, Neravy
4. Thiru. R. Sakthivel, 114 Church Street, Karaikal.
5. Thiru N.Vengadesan, Kathiravan electrical 108, Gnanapragasam street , Karaikal.
6. Notice Board

Copy to:

1. The Junior Engineer/Town- O&M, Electricity Department, Karaikal
2. The National Informatics Officer, National informatics centre, O/O. The Collector, Karaikal.

Copy submitted to:

The Executive Engineer-V
 Electricity Department,
 Karaikal