



GOVERNMENT OF PUDUCHERRY
ELECTRICITY DEPARTMENT
KARAIKAL

L.C.O. No. 14 / EDK / AE-Town-I / F / 2017-18

Dt. 23.10.2017

QUOTATION NOTICE

Sub: EDK – Estimate for Provision of one no. of 100 KVA Transformer namely Keezhavanjoure SS XI for extension of power supply to one no. of Pisciculture (D2) service connection for a connected load of 60 HP in favour of Thiru. N.Murali, M/s. Murali Aqua Farm at Keezhavanjoure, T.R.Pattinam in Karaikal – Quotation Called for - Reg.


Sealed Quotations are here by invited by the Assistant Engineer / Town-I, Electricity Department, , Karaikal on behalf of the President of India, from the contractors experienced in the same field of works for the works given below. The Quotations should reach the office on or before 10.00 A.M. of 30.10.2017 and the same will be opened at 11.00 A.M. on the next working day in the chamber of Assistant Engineer / Town-I. Those tenderers who are willing may be present at the time. If the opening date happens to be a Holiday, the next working day will be treated as the opening day.

Name of the work: Estimate for Provision of one no. of 100 KVA Transformer namely Keezhavanjoure SS XI for extension of power supply to one no. of Pisciculture (D2) service connection for a connected load of 60 HP in favour of Thiru. N.Murali, M/s. Murali Aqua Farm at Keezhavanjoure, T.R.Pattinam in Karaikal

Sl. No.	Description of Item	Approx. Qty.	Unit Rate	Amount
1.	Labour charges for the erection of 10' center D.P. structure with 30' RCC poles, complete with erection of AB switch, HG fuses, Lightening arrester, Jumpering, SS Earthing, Pole concreting as per specification, LT feeding arrangements and coping including the supply of blue metal, sand and water required for the concreting of the pole by adopting a mixing ratio 1: 3: 6, painting of the poles and coping with Snow Cem and the metal parts of the structure with aluminium paint, including the cost of transportation of the materials from the Department stores to the work site. Poles and Transformer to be transported from Sorakudy SS to the work site	01 No.		
2.	Transportation of 30' RCC pole from Sorakudy pole casting yard to the work spot	05 Nos.		
3.	Transportation of Stay block with rod from Sorakudy pole casting yard to the work spot	08 Nos.		
4.	Erection of 30' RCC (without Concreting) including earthing, excavation and refilling (GI wire will be supplied by the department)	05 Nos.		
5.	Concreting of 30' RCC pole in cement concrete foundation (0.45 x 0.45 x 1.5) mts. and coping (0.45 x 0.45 x 0.45) mts. With ratio 1:3:6 using 20mm HBG metal including cost of concreting materials such as	05 Nos.		

GOVT. OF INDIA
MUNICIPAL DISTRICT UNIT,
KARAIKAL
RECEIVED DATE: 26.10.17

Sl. No.	Description of Item	Approx. Qty.	Unit Rate	Amount
	cement, jelly, sand etc. including earthing, excavation and refilling (GI wire will be supplied by the department)			
6.	Errrection of HT / LT Stay set without Concreting	08 Nos.		
7.	Fixing of HT Tapping channel (75 x 45 x 10) mm for 11 KV overhead line including drilling of holes for Insulator	04 Nos.		
8.	Fixing of V cross arm in RCC pole for 11 KV overhead line	05 Nos.		
9.	Errrection of 11 KV Pin Insulator with G.I.Pin	15 Nos.		
10.	Errrection of F clamp in poles for 11 KV overhead line	05 Nos.		
11.	Errrection of 11 KV disc insulators for 11 KV overhead line complete with 11 KV metal Parts as required	12 Nos.		
12.	Errrection of ACSR conductor of 7/3.35 Sq.mm diametre	124 Mts.		
13.	Errrection of ACSR conductor of 7/2.59 Sq.mm diametre	762 Mts.		
14.	Errrection of 3 Ph cross arm with pole clamp	04 Nos.		
15.	Errrection of LT Pin Insulator with GI Pin , CI Knob & L Clamp	04 Nos.		
16.	Errrection of LT Shackle Insulator with Metal parts	12 Nos.		
17.	Supply of 30' RCC poles as per specification detailed in the annexure enclosed	07 Nos.		
18.	Supply of ACSR 7/3.35 Conductor as per specification detailed in the annexure enclosed	124 Mts.		
19.	Supply of ACSR 7/2.59 Conductor as per specification detailed in the annexure enclosed	762 Mts.		


 Assistant Engineer / Town I
 Electricity Department
 Karaikal

Terms and Conditions:

1. The work should be completed within 90 days from the date of receipt of the work order.
2. The payment will be made within 30 days on completion of the work satisfactorily and on receipt of the proper bill.
3. The work shall be carried out under the direct supervision of grade 'A' electrical contractor.
4. After the fabrication of grill for 30' RCC poles the same is to be inspected by the Assistant Engineer / Town-I and Junior Engineer / T.R.Pattinam. Only obtaining clearance of the above Engineers the concreting of poles is to be carried out.
5. GST & Service Tax shall be quoted separately for supply of materials and labour.

To

1. Thiru. M.Jeevanandan, 01 Church Street, Karaikal
2. Thiru. S.Kathamuthu, 58 Thoodhuponamoolai, Alathur (Post), Karaikal
3. Thiru. V.Ranjith, 04 Pillaiyar Kovil Street, Thoodhuponamoolai, Neravy, Karaikal
4. Thiru. R.Sakthivel, 114 Church Street, Karaikal
5. Thiru. N.Vengadesan (Kathiravan Electricals), 108 Gnanapragasam Street, Karaikal
6. Thiru. P.Selvakumar, 19 River Street, Valathamangalam, Karukkankudy, Thirunallar
7. Thiru. MU.Selvam, 84 Mariamman Kovil Street, Thiru Nagar, Karaikal
8. M/s. Karthik Enterprises, 04 Laporte Street, Municipal Complex, Puducherry
9. M/s. Mechlein Engineers, Jaya Nagar, Reddiyarpalayam, Puducherry
10. Thiru. M.S.Ravikumar, 33/5 Rajiv Nagar, Thenoor, Thirunallar, Karaikal
11. M/s. Eswari Electricals, 21- III Cross, Vallalar Street, PK Salai, Kovilpathu, Karaikal
12. Thiru. V.K.Ramadoss, M/s.Golden Engg. & Consultancy, 82 Bharathiyar Road, Karaikal
13. Notice Board

Copy to:

1. The Junior Engineer
T.R.Pattinam O&M

- ✓ 2. The National Information Officer – With a request to put up in the Karaikal Web site
National Informatics Centre
O/o. The Collector, Karaikal

✓ Copy Submitted to:

1. The Executive Engineer Div. V
Electricity Department
Karaikal