

KOTTUCHERRY COMMUNE PANCHAYAT
SCHEDULE OF QUANTITIES

Name of work : Construction of Community Hall at Anna Nagar in Kottucherry.

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
1	Supplying and filling with good earth (excluding rock) in layers not exceeding 20cm in depth, breaking clods, watering, rolling each layer with 1/2 tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes capacity including all leads and lift (payment will be made based on level measurement). Deduct for not rolling with power roller of minimum 8 tonnes for banking excavated earth in layers not exceeding 20cm in depth. Deduct for not watering the excavated earth for banking.	138.00 Cum	1 Cum (One Cubic Metre)			
2	Earthwork in excavation in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m all kinds of soil.	68.00 Cum	1 Cum (One Cubic Metre)			
3	Filling available excavated earth (excluding rock) in trenches, plinth sides of foundation etc., in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering lead upto 50mt. and lift upto 1.50mt.	68.00 Cum	1 Cum (One Cubic Metre)			
4	Supplying and filling with good earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in deapth consolidating each deposited layers by ramming and watering etc. complete including all lead and lift.	39.00 Cum	1 Cum (One Cubic Metre)			
5	Supplying and filling in plinth with river sand under floors inclduing, watering, ramming consolidating and dressing complete.	16.00 Cum	1 Cum (One Cubic Metre)			
6	Providing and laying in position cement concreete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:5:10 (1 cement : 5 sand : 10 graded stone aggregate 40mm nominal size).	9.00 Cum	1 Cum (One Cubic Metre)			
7	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work upto plinth level - 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm nominal size).	15.00 Cum	1 Cum (One Cubic Metre)			

8 Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upto floor five level excluding cost of centring, shuttering, finishing and reinforcement - 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm nominal size).

3.00 Cum 1 Cum (One Cubic Metre)

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15 degree, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral staircases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size).	20.00 Cum	1 Cum (One Cubic Metre)			
10	Centring and shuttering including strutting, propping etc. and removal of form for - suspended floor, roofs, landings, balconies and access platform.	111.00 Sqm	1 Sqm (One Square Metre)			
11	Centring and shuttering including strutting, propping etc. and removal of form for - foundations, footings, bases of columns etc. for mass concrete.	2.00 Sqm	1 Sqm (One Square Metre)			
12	Centring and shuttering including strutting, propping etc. and removal of form for - lintels, beams, plinth beams, girders, bressummers and cantilevers.	99.00 Sqm	1 Sqm (One Square Metre)			
13	Centring and shuttering including strutting, propping etc. and removal of form for - columns, pillars, piers, abutments, posts and struts.	50.00 Sqm	1 Sqm (One Square Metre)			
14	Centring and shuttering including strutting, propping etc. and removal of form for - stairs, excluding landings) except spiral - staircases.	12.00 Sqm	1 Sqm (One Square Metre)			
15	Providing, hoisting and fixing upto floor five level precast reinforced cement concrete in shelves including setting in cement mortar 1:3 (1 cement : 3 sand), cost of required centring, shuttering and finishing with neat cement punning on exposed surfaces but excluding the cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 12.5mm nominal size).	0.83 Cum	1 Cum (One Cubic Metre)			
16	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete - Thermo Mechanical Treated Bars (TMT) TISCON / VIZAG / IISCO / SAIL.	2350.00 Kgs.	1 Kg. (One Kilogram)			
17	Brick with bricks of class designation 35 in foundation and plinth in cement mortar 1:4 (1 cement: 4 sand).	10.00 Cum	1 Cum (One Cubic Metre)			

18	Bricks work in superstructure above plinth level upto floor five level - Cement mortar 1:4 (1 cement : 4 sand)	0.70 Cum	1 Cum (One Cubic Metre)
19	Bricks work in superstructure above plinth level upto floor five level - Cement mortar 1:6 (1 cement : 6 sand)	32.00 Cum	1 Cum (One Cubic Metre)
20	Half brick masonry with bricks of class designation 35 in foundation and plinth in - cement mortar 1:4 (1 cement : 4 sand).	31.00 Sqm	1 Sqm (One Square Metre)

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
21	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position - country wood (Padak).	0.44 Cum	1 Cum (One Cubic Metre)			
22	Providing and fixing panelled or panelled and glazed shutters for doors windows and clearestory windows, panelling which will be paid for separately - Country wood (Padak) 40mm thick.	20.00 Sqm	1 Sqm (One Square Metre)			
23	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25mm to 40mm thick - Country wood (Padak).	20.00 Sqm	1 Sqm (One Square Metre)			
24	Providing and fixing M.S. grills of required patterns in frames of windows etc., with MS flats or square or round bars etc. all complete fixed to openings / wooden frames with rawl plugs.	245.00 Kg	1 Kg. (One Kilogram)			
25	Providing 40x5mm flat iron hold fast 40cm long including fixing to frame with 10mm diameter bolts, nuts and wooden plougs and embeddings in cemnent concrete block 30x10x15 CM 1:3:6 (1 cement : 3 sand : 6 graded stone aggregate 20mm nominal size)	66.00 Nos	1 No. (One Number)			
26	Providing and fixing aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete - 125 x 75 x 4mm.	30.00 Nos	1 No. (One Number)			
27	Providing and fixing aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete - 75 x 45 x 3.2mm.	48.00 Nos	1 No. (One Number)			
28	Providing and fixing aluminium sliding door bolts anodised (anodic coating not less than grade AC 10 as per IS 1868) transparent or dyed to required colour or shade with nuts and screws etc., complete - 300 x 16mm.	6.00 Nos	1 No. (One Number)			

29	Providing and fixing aluminium tower bolts anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour shade with necessary screws etc., complete - 250x 10mm.	10.00 Nos	1 No. (One Number)
30	Providing and fixing aluminium tower bolts anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with necessary screws etc., complete - 100x 10mm.	24.00 Nos	1 No. (One Number)
31	Providing and fixing aluminium handles anodised (anodic coating not less than grade AC 10 as per IS 1868) transparent or dyed to required colour or shade with necessary screws etc., complete 125mm.	10.00 Nos	1 No. (One Number)

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
32	Providing and fixing MS hooks and eyes conforming to IS 207- 100mm.	18.00 Nos	1 No. (One Number)			
33	Providing and fixing godrej nov-tal lock-65mm size	6.00 Nos	1 No. (One Number)			
34	Providing and fixing M.S. fan clamp type -i of 16mm dia m.s. bar bent to shape with hooked ends in R.C.C. slabs during laying including painting the exposed portion of loop, all as per standard design complete.	7.00 Nos	1 No. (One Number)			
35	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry. but excluding the cost of nosing of steps etc. complete 40mm thick with 20mm nominal size stone aggregate.	64.00 Sqm	1 Sqm (One Square Metre)			
36	Painting top of roofs with bitumen of approved quality at 17Kg/10Sqm impregnated with a coat of coarse sand at 60cudm/10sqm including cleaning the slab surface with brushed and finally with a piece of cloth lightly soaked with kerosene oil complete - with residual type petroleum bitumen of penetration 80/100.	66.00 Sqm	1 Sqm (One Square Metre)			
37	Providing and laying pressed clay tiles (as per approved pattern 20mm nominal thickness and of approved size) on roofs jointed with cement mortar 1:4 (1 cement : 4 coarse sand) mixed with 2% integral water proffing compound laid over a bed of 20mm cement mortar 1:4 (1 cement : 4 coarse sand) and finished neat complete.	73.00 Sqm	1 Sqm (One Square Metre)			
38	Lime concrete terracing on roofs of required thickness laid to fall with 25mm nominal size brick aggregate and 50% lime mortar 1:2 (1 lime putty : 2 surkhi) rammed and finished with gur and belgiri treatment complete including rounding of junctions with parapet wall	8.00 Cum	1 Cum (One Cubic Metre)			

39	Providing and fixing on wall face/column unplasticised - PVC (working pressure 4kg/sqcm) rain water pipes conforming to IS :13592 including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion. single socketed pipes 110mm diameter.	38.00 Rmt	1 Rmt (One Running Metre)
40	Providing and fixing unplasticised-PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50mm hard wood plugs, screwed with M.S. screws of required length including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 sand) and making good the walls etc. complete.	30.00 Nos.	1 No. (One Number)
41	Providing and fixing on wall face/column face unplasticised - PVC moulded fittings/accssories for unplasticisd - PVC rain water pipes conforming to IS : 13592 including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion - bend 87.5 degree - 110 mm bend.	6.00 Nos.	1 No. (One Number)

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
42	Providing and fixing on wall face/column face unplasticised - PVC moulded fittings/accssories for unplasticisd - PVC rain water pipes conforming to IS : 13592 including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion 110mm dia shoe plain.	9.00 Nos.	1 No. (One Number)			
43	12mm cement plaster of mix 1:4 (1 cement : 4 coarse sand)	36.00 Sqm	1 Sqm (One Square Metre)			
44	15mm cement plaster on the rough side of single or half brick wall of mix 1:6 (one cement and six fine sand)	211.00 Sqm	1 Sqm (One Square Metre)			
45	6mm cement plaster to ceiling of mix 1:3 (one cement and three fine sand)	138.00 Sqm	1 Sqm (One Square Metre)			
46	12mm cement plaster on the rough side of single or half brick wall of mix 1:6 (one cement and six sand)	185.00 Sqm	1 Sqm (One Square Metre)			
47	Finishing walls with water proofing cement paint of approved brand and manufacture and of required shade to give an even shade new work (three or more coats).	432.00 Sqm	1 Sqm (One Square Metre)			
48	White washing with whiting to give an even shade new work (three or more coats).	138.00 Sqm	1 Sqm (One Square Metre)			
49	Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade - new wood work (two or more coats)	45.00 Sqm	1 Sqm (One Square Metre)			
50	Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade - new steel work (two or more coats)	15.00 Sqm	1 Sqm (One Square Metre)			

51	Providing and fixing white vitreous china water closet squatting pan (Indian type) - Orissa pattern W.C. pan of size 580 x 440mm	2.00 Nos.	1 No. (One Number)
52	Providing and fixing white vitreous china wash basin including making all connections but excluding the cost of fittings - Flate back wash basin of size 450 x 300mm Parryware / Hindware.	2.00 Nos.	1 No. (One Number)
53	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete - flexible pipe 32mm dia.	2.00 Nos.	1 No. (One Number)
54	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc.(internal work) exposed on walls - 20mm nominal bore (1.58 kg/m).	80.00 Mts.	1 Mt. (One Metre)
55	Providing and fixing G.I.pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. (internal work) exposed on wall - 32 mm nominal bore. (3.17 kg/m).	18.00 Mts.	1 Mt. (One Metre)

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
56	Providing and fixing G.I.pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. (internal work) - 40mm nominal bore (3.61 kg/m).	20.00 Mts.	1 Mt. (One Metre)			
57	Providing and fixing brass bib cock of approved quality - 15 mm nominal bore.	7.00 Nos.	1 No. (One Number)			
58	Providing and fixing gun metal non-return valve of approved quality (screwed end) - 40 mm nominal bore - vertical.	1.00 No.	1 No. (One Number)			
59	Providing and fixing ball valve (brass) of approved quality complete - high or low pressure with plastic floats - 20 mm nominal bore.	1.00 No.	1 No. (One Number)			
60	Providing and fixing brass gate valve with C.I. wheel of approved quality (screwed end) - 20mm nominal bore	2.00 No.	1 No. (One Number)			
61	Providing and fixing brass gate valve with C.I. wheel of approved quality (screwed end) - 32mm nominal bore.	1.00 No.	1 No. (One Number)			
62	Providing and fixing in position UPVC moulded saddle set (Finolex/Jain)(0.6 Mpa) conforming to IS 7834 part II and ISI marked,including labour charges for jointing, jointing materials etc,complete - 110 x 20mm dia	1.00 No.	1 No. (One Number)			
63	Providing and placing on terrace (at all floor levels) polyethylene water storage tank of approved brand and manufacture with cover and suitable locking arrangement and making necessary holes for inlet, outlet, over flow pipes with all fittings but without the base support for tank (Sintex JSJ)	1000.00 Lts.	1 Lt. (One Litre)			

64	Supplying fixing and commissioning of Suguna / Texmo / Sharp 1 HP monoblock pumpset slow speed single phase motor. The rate include the cost of pumpset, pumpset fixing in position and test run etc. complete as directed by the engineer in charge.	1.00 No.	1 No. (One Number)
65	Construction of sump of internal size 3.00x1.25x1.80m including earthwork excavation and laying cement concrete 1:4:8 - 25cm deep including consolidation curing etc., complete walls are to be constructed in brick work in cement mortar 1:4 to a thick of 34cm and a depth of sump shall be finished with cement concrete 1:2:4 - 75mm thick internal and external size of sump shall be plastered with cement concrete mortar 1:3 of 20mm thick with water proofing compound material at the rate of 2% of weight of cement. The top of the sump shall be covered in RCC slab in CC 1:2:4 - 10cm thick the rate including the centring, shuttering and required reinforcement. The bottom and top surface of the slab shall ve finished with C.M 1:3 to give an even smooth surface but not exceeding 6mm thick. The monhole cover with frame of 65 x 45cm shall be provided at the top of the slab with all accessories, the manhole cover shall not less than 30Kg (light duty).	1.00 No.	1 No. (One Number)
66	Making soak pit 2.5m diameter 3.0 metre deep with 45x45cm dry brick honey comb shaft with bricks of class designation 35 and S.W drain pipe 100mm diameter, 1.8m long complete as per standard design - with brick of class	1.00 No.	1 No. (One Number)

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
67	Construction of septic tank of internal size 2.30 x 1.10 x 1.64m with necessary earth work excavation 23cm thick foundation concrete 1:4:8 (one cement, four sand and eight 40mm HBG metal) 45cm thick masonry wall allround upto a height of 1.50mt. and 34cm thick wall for the remaining height upto 0.45 height upto 0.45 height in C.M. 1:4 (one cement and four sand) inlet and outlet chambers will be of internal size 45cm x 45cm x 45cm with brick work in C.M. 1:4 (one cement and four sand) including CI manual cover and dwarf wall 188cmx120cmx11cmx11cm in C.M. 1:4 (one cement andn four sand) and RCC baffle wall of 146cm x 120cm x 7.5cm. Plastering the sides of the septic tank and chambers will be with cement mortar 1:3, 12mm thick, top of tank will be covered with precast slab of RCC 1:2:4, 12mm thick. The bottom of the tank is to be floored with C.C.1:2:4 to proper slope and finished neatly. The cost of construction excludes fixing the ventilation shaft etc., complete all as per the instruction of the Engineer-in-charge.	1.00 No.	1 No. (One Number)			
68	Providing and fixing 600 x 450 mm bevelled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	1.00 No.	1 No. (One Number)			
69	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 metres	31.31 Cum	1 Cum (One Cubic Metre)			
70	Demolishing R.C.C work including stacking of steel bars and disposal of unserviceable material within 50 metres lead.	8.82 Cum	1 Cum (One Cubic Metre)			

71	Demolishing cement concrete including disposal of material within 50 metres	3.69 Cum	1 Cum (One Cubic Metre)
72	Taking out doors and Windows & clearstorey windows shutters (steel or wood) including stacking within 50 metres lead of area 3 sqm and below.	10.00 Nos.	1 No. (One Number)
73	Supplying and fixing of following size of PVC conduit alongwith the accessories in surface/recess Conduit including cutting the wall and making good the same in case of recessed conduit as required. Make: Avonplast /Vijaya:- 25mm dia	96.00 Mts.	1 Mt. (One Metre)
74	Supplying and fixing of following size of PVC conduit alongwith the accessories in surface/recess Conduit including cutting the wall and making good the same in case of recessed conduit as required. Make: Avonplast/Vijaya:- 32mm dia	10.00 Mts.	1 Mt. (One Metre)
75	Supplying and laying of following size of PVC conduit in roof slab alongwith the accessories. Make: Avonplast/Vijaya:- 25mm dia	72.00 Mts.	1 Mt. (One Metre)
76	Supplying and drawing of 1.5 sqmm. FR PVC insulated, copper conductor, single core cable in the existing surface / recessed, PVC/steel conduit/PVC casing and capping as required.Make: Finolex/ Polycab:-	240.00 Mts.	1 Mt. (One Metre)
77	Supplying and drawing of 2.5 sqmm. FR PVC insulated, copper conductor, single core cable in the existing surface / recessed, PVC/steel conduit/PVC casing and capping as required.Make: Finolex/ Polycab:-	10.00 Mts.	1 Mt. (One Metre)

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
78	Supplying and fixing of following size of PVC deep junction box in required position along the line of PVC conduit as required .Make:Avonplast/Vijaya:- 25mm deep Junction Box one way.	5.00 Nos.	1 No. (One Number)			
79	Supplying and fixing of following size of PVC deep junction box in required position along the line of PVC conduit as required .Make:Avonplast/Vijaya:- 25mm deep Junction Box two way.	5.00 Nos.	1 No. (One Number)			
80	Supplying and fixing of following size of PVC deep junction box in required position along the line of PVC conduit as required .Make:Avonplast/Vijaya:- 25mm deep Junction Box three way.	4.00 Nos.	1 No. (One Number)			
81	Supplying and fixing of following size of PVC deep junction box in required position along the line of PVC conduit as required .Make:Avonplast/Vijaya:- 25mm deep Junction Box four way.	4.00 Nos.	1 No. (One Number)			
82	Supplying and fixing of following size of PVC junction box in required position along the line of PVC conduit as required.Make:Avonplast/Vijaya:- 25mm Junction Box one way	14.00 Nos.	1 No. (One Number)			
83	Supplying and fixing of following size of PVC junction box in required position along the line of PVC conduit as required.Make:Avonplast/Vijaya:- 25mm Junction Box two way	2.00 Nos.	1 No. (One Number)			

84	Supplying and fixing of following size of PVC junction box in required position along the line of PVC conduit as required. Make: Avonplast/Vijaya:- 25mm Junction Box three way	2.00 Nos.	1 No. (One Number)
85	Supplying and fixing of following size of PVC junction box in required position along the line of PVC conduit as required. Make: Avonplast/Vijaya:- 25mm Junction Box four way	2.00 Nos.	1 No. (One Number)
86	Supplying and fixing of following size of steel conduit alongwith accessories in surface/recess including painting in case of surface conduit or cutting the wall and making good the same in case of recessed, conduit as required :- 32mm	5.00 Mts.	1 Mt. (One Metre)
87	Supplying and fixing of the following sizes of Teak wooden board on recess including cutting the wall and finishing the surface good the same as required - 375mm X 300mm X 50mm. Deep	4.00 Nos.	1 No. (One Number)
88	Supplying and fixing of the following sizes of Teak wooden board on recess including cutting the wall and finishing the surface good the same as required - 150mm X 150mm X 50mm. Deep	1.00 No.	1 No. (One Number)
89	Providing and fixing of following size phenolic coated sheet on existing wooden board: - 375mm X 300mm X 3mm Thick	4.00 Nos.	1 No. (One Number)
90	Providing and fixing of following size phenolic coated sheet on existing wooden board: - 150mm X 150mm X 3mm Thick	1.00 No.	1 No. (One Number)

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
91	Supplying and fixing S.P 1 way 5/6amps piano/flush type switch on the existing switch box /cover including connections etc. as required. Make: Kundan /Anchor /Vinay :-	26.00 Nos.	1 No. (One Number)			
92	Supplying and fixing 3 pin 5/6amps piano/flush type socket outlet on the existing switch box/cover including connections etc. as required. Make: Kundan / Anchor/Vinay:-	2.00 Nos.	1 No. (One Number)			
93	Supplying and fixing 3 pin 15/16amps piano/flush type socket outlet on the existing switch box/cover including connections etc. as required. Make: Kundan /Anchor /Vinay:-	3.00 Nos.	1 No. (One Number)			
94	Supplying and fixing S.P 1 way 15/16amps piano/flush type socket outlet on the existing switch box/cover including connections etc. as required. Make: Kundan /Anchor /Vinay:-	3.00 Nos.	1 No. (One Number)			
95	Supplying and fixing 5/6amps indicator on the existing switch box/cover including connections etc. as required. Make: Kundan/Anchor/Vinay:-	3.00 Nos.	1 No. (One Number)			

96	Supplying and fixing 10 amps Kit Kat Fuse on the existing switch box/cover including connections etc. as required. Make: Kundan/Anchor/Vinay:-	3.00 Nos.	1 No. (One Number)
97	Supplying and fixing 16 amps Kit Kat Fuse on the existing switch box/cover including connections etc. as required. Make: Kundan/Anchor/Vinay:-	1.00 Nos.	1 No. (One Number)
98	Supplying and fixing Electronic Dimmer 400W socket type on the existing switch box/cover including connections etc as required Make: Kundan/Anchor/Vinay.	7.00 Nos.	1 No. (One Number)
99	Supplying and fixing jumbo type Batten/Angle Holder including connections etc. as required .Make: Kundan/Anchor/Vinay:-	3.00 Nos.	1 No. (One Number)
100	Supplying and fixing 3 plate, 5 amp.ceiling rose on the existing junction box/wooden block including connections etc. as required.Make: Kundan/Anchor/Vinay:-	30.00 Nos.	1 No. (One Number)
101	Installation, testing and commissioning of prewired, all kind of surface mount light fittings, complete with all accessories etc.directly on high ceiling/wall, including connections with 16/0.20mm twin core FR PVC sheathed flat flexible, copper cable etc. as required.	17.00 Nos.	1 No. (One Number)
102	Installation, testing and commissioning of prewired, all kind of surface mount light fittings, complete with all accessories etc.directly on high ceiling/wall, including connections with 16/0.20mm twin core FR PVC sheathed flat flexible, copper cable etc. as required.	7.00 Nos.	1 No. (One Number)

Sl. No	Sub heads and item of work	Quantity	Per	Rate		Amount
				Figure	Words	
103	Supplying and fixing 32 Amps single phase D.P. Pilot switch with indicator (surface/recessed) on the existing switch box/cover including connections etc., as required: Make: Kundan.Anchor/Vinay.	1.00 No.	1 No. (One Number)			
104	Earthing with G.I.medium pipe 3.0 mt long and 40mm dia including accessories 250 x 50 x 6 mm G.I clamp with 12mm bolt, nut and washer for connecting earth wire, RCC ring enclosure and cover plate complete as required:-	1.00 No.	1 No. (One Number)			
105	Service connection from electricity department supply post to department metre single phase line including labour charges 3/20 PVC insulated copper wire 7/10 G.I. wire parcel in reel etc., as required.	50.00 Mts.	1 Mt. (One Metre)			
106	1400mm sweep double ball bearing ceiling fan Make : Almonard/Usha.	7.00 Nos.	1 No. (One Number)			
107	1 x 40W box type single tube light fitting with copper choke & starter without tube. Make: Philips / Bajaj. 40W tube light Make : Philips.	8.00 Nos.	1 No. (One Number)			

108 Bulk head fitting aluminium alloy body heat resistant prismatic glass cover with specially designed gasket GLS 100W type). Make : Philips / Bajaj.	4.00 Nos.	1 No. (One Number)
109 32A cutout fuse unit Make: Kundan.	1.00 No.	1 No. (One Number)